

CHITALDROOG DIVISION.

ADVERTISEMENT.

The 23rd March 1893.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldroog Division, up to 10th April 1893, for constructing a new Taluk Cutcherry at Challakere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1895.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldroog, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

| Description of Work. | Per. | Quantity. |
|---|-----------|-----------|
| Stone in chunam | C. Ft. | 12,258 |
| Brick in chunam | Do | 20,020 |
| Slab stone work | Do | 483 |
| Arch work (Brick in chunam) | Do | 468 |
| Cornice work | R. Ft. | 1,128 |
| Plastering with chunam | Sq. | 269.32 |
| White washing | Do | 144.71 |
| Color washing | Do | 124.61 |
| Roofing with Mangalore tiles, teak reepers, &c. | Do | 70.24 |
| Flat Terrace roofing | Do | 1.56 |
| Bengal Terrace | Do | 13.32 |
| Concrete, Flooring including plastering | Do | 41.88 |
| Gravel flooring | C. Yds. | 8 |
| Wood work teak | C. Ft. | 542 |
| Earthwork foundation excavation | Do | 522 |
| Filling in basement | L. S. Rs. | .. |
| Iron (wrought) | lbs. | 373 |
| Painting (chocolate) | Sq. | 28.74 |
| Wood-oiling two coats | Do | 41.48 |
| Bamboo matting | Do | 28.87 |
| Door to Treasury room 3' x 6' with iron, &c. | Each. | 1 |
| Door, small, 3' x 6' pannelled.. .. . | Do | 17 |
| Do 3' x 6' battened | Do | 5 |
| Do large, 5' x 6' do | Do | 1 |
| Do large, 5' x 6' do | Do | 16 |
| Windows, large, 3' x 3½' iron bars, &c. | Do | 2 |
| Do ventilators 3½' x 1½' do | Do | 10 |
| Do pannelled 3' x 3½' do | Do | 7 |
| Do battened with iron bars 3' x 1½' | Do | 9 |
| Do do 2' x 1½' | C. Ft. | 23 |
| Brick in chunam | Sq. | 340 |
| Flagging | R. Ft. | 54 |
| Ornamental cornice | L. S. | .. |
| Date stone | Do | .. |
| Gate with iron work, complete | No. | 5 |
| Ornamental finials | Do | 8 |
| Ornamental stone pillars at the entrance | L. S. | .. |
| Wooden screen | Do | .. |
| Wooden railings | Do | .. |
| Drainages, &c. | Do | .. |
| Zinc gutters at valleys | R. Ft. | 60 |

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new Taluk Cutcherry at Challakere", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. RANGA RAO,
Offg. Executive Engineer.